

ESSEX-WINDSOR SOLID WASTE AUTHORITY

REQUEST FOR TENDER

FOR

REGIONAL LANDFILL CELL 3 SOUTH CONSTRUCTION, CONTRACT 8

SEALED TENDERS, in envelopes clearly marked as to the contents and showing the bidder's company name, will be received by:

Mr. Tom Marentette, P. Eng., Manager of Waste Disposal, Essex-Windsor Solid Waste Authority
360 Fairview Ave. West, Suite 211, Essex, Ontario, Canada N8M 3G4

The Tender closing date is Thursday April 19, 2018, at 12:00 noon local time.

Those interested in bidding are requested to attend a **mandatory meeting** on site on **one of the following dates: Thursday March 22, 2018 at 10:00 a.m. or Thursday March 29, 2018 at 10:00 a.m.**, at the Essex-Windsor Solid Waste Authority, Regional Landfill, located at 7700 County Road 18, Town of Essex (former Colchester North Township, between Coulter Rd. and Ferris Side Rd.). Contractors are to check in at the Scale House upon entering the site. **Bids will not be opened from any company who did not have a representative at the mandatory site meeting.**

Please direct any questions or concerns pertaining to the tender to Mr. Tom Marentette, P. Eng., Manager of Waste Disposal by email tommarentette@ewswa.org or by phone 519-776-6441, ext. 1961, up until Monday, April 16, 2018.

The work consists of the following major items:

1. Earth excavation (grading) including waste, clay cap application, separation berm, clay haul roads and disposal/stockpiling of excess soil - 429,320 m³
2. Base excavation for removal of unsuitable materials (sand) and backfill with clay liner - 8,000 m³
3. Supply and place geotextile separator - 53,850 m²
4. Supply and place drainage gravel - 19,960 m³
5. Supply and install leachate collection system consisting of 200 mm dia. HDPE piping and manholes with all specified accessories - 2,047 m
6. Full depth asphalt pulverizing – 24,406 m²
7. Road reconstruction (paved and gravel surfaces) and associated work including drainage ditches – 1,765 m
8. Construction of asphalt compost processing pad - 33,050 m²
9. Miscellaneous drainage ditching, CSP culverts, including rip-rap
10. Placement of topsoil, fertilize and seed several areas
11. Litter fencing and bird over-wiring system poles
12. Other miscellaneous work including electrical, chain-link fencing, removals, roadwork repairs and erosion control measures.

Each tender must be accompanied by a tender deposit in the form of a certified cheque or Bid Bond as per the tender requirements, along with a signed Agreement to Bond for 100% Performance and 50% Labour and Material Payment.

Tender documents, including maps, can be found on the Authority's website at:

<http://www.ewswa.org/about/business-opportunities-bids/>

(AutoCAD versions of drawings are available upon request)

Alternatively, paper copies can be obtained at the Authority's office at 360 Fairview Ave. West, Suite 211, Essex, ON. The cost is \$100 including HST (cash or cheque only please). The fee is non-refundable.

Lowest or any tender will not necessarily be accepted and is conditional upon acceptance of the Essex-Windsor Solid Waste Authority Board.



1821 Provincial Road, Suite 100
Windsor, ON N8W 5V7
Attention: Radwan Tamr, M.S., P.Eng., QP_{ESA}
Tel: (519) 974-5887 ext. 224



360 Fairview Ave. West, Suite 211
Essex, ON N8M 3G4
Attention: Tom Marentette, P. Eng.
Tel: (519) 776-6441 ext. 1961